

July 16, 2018

CONSTRUCTION NOTICE #5: Port Lands Flood Protection

Partial Lane Closures: Sunday July 22 to Friday July 27

Surveys to inspect and document underground utilities will require partial lane closures for periods of one hour at a time. From Sunday, July 22 to Friday, July 27 between the hours of 8:00 a.m.-3:30 p.m., crews will be working on the following streets:

Location:

1. Lake Shore Boulevard East (between Cherry Street and Saulter Street)
2. Villiers Street (between Cherry Street and Saulter Street)
3. Commissioners Street (between Cherry Street and Saulter Street)
4. Munitions Street (between Villiers Street and Commissioners Street)
5. Don Roadway (between Lake Shore Boulevard and Commissioners Street)
6. Saulter Street (between Lake Shore Boulevard and Commissioners Street)

PORT LANDS FLOOD PROTECTION – PROGRESS UPDATE

Site preparation: July 2018 to September 2018



The map above shows the areas where work has started and will continue throughout the summer. Please note area boundaries are approximate.

Area 1: Construction crews are preparing to start demolition at Commissioners Street and Cherry Street. Existing asphalt and concrete, as well as existing buildings at that site, will be removed. Tree cutting is scheduled for August 2018. During tree cutting, we will work with Toronto and Region Conservation to ensure birds and bats are protected.

Area 2: Construction on a temporary structure to separate work zones along the River Valley and Don Greenway will start in September.

Area 3: Tree cutting is scheduled for August 2018. During tree cutting, we will work with Toronto and Region Conservation to ensure birds and bats are protected.

In addition to this activity, site preparation work is also ongoing at a number of locations in the Port Lands. This includes drilling to collect soil and groundwater samples, surface water sampling, land surveying, pilot testing for soil treatment technologies, geophysical surveys, and vegetation and wildlife surveys

CHERRY STREET LAKEFILLING – PROGRESS UPDATE

Work continues on dock wall construction, lakefilling and marine landscaping.



Crews have completed installing the pipe and sheet piles that will support the new dock wall. Later this month the crew will start to install the rock anchor, which will involve cutting the pipe and sheet piles, installing the casing and drilling. The drilling will be vibratory, which keeps noise to a minimum.



Lakefilling continues in Cell 2 and 3 (shown in the graphic above). A total of 4,867 truckloads of locally sourced, clean fill has been added to Cell 2 so far.



Crews continue to shape the core stone – the aggregate that makes up the new shoreline. The west cove along the new shoreline has now been formed – future home to fish and other aquatic habitat. The team will start placing armor stone along the shoreline this month, which will secure the shoreline.

QUESTIONS:

To learn more about this project, please visit portlandsto.ca. Use this [online form](#) to send us questions or concerns about construction or email us at plfp@ellisdon.com. For urgent construction related issues, please contact Cameron Coleman, EllisDon, at 416-464-3583.